

**MISHRA DHATU NIGAM LIMITED  
P.O.KANCHANBAGH, HYDERABAD**

**Part-II (PRICE BID)**

**CIVIL WORKS FOR REVAMPING OF 1500T PRESS,  
MIDHANI,  
KANCHANBAGH, HYDERABAD-58.**

**PURCHASE DEPARTMENT****Tender Notice No: MDN/PUR/AP20/ADVT/280/16-17****Date:-17-01-2017****To,**

Dear Sir,

**Sub: - CIVIL WORKS FOR REVAMPING OF 1500T PRESS, MIDHANI,  
- reg**

1. Please find enclosed herewith a Tender Enquiry for the above, you are requested to furnish your offer in a sealed cover superscripting the envelope with name of work and last date of submission, along with EMD of Rs 1,17,000/- drawn in favour of MIDHANI. The tenders without EMD amount will be rejected; request for adjustment from pending bills will not be entertained. Estimated Value of work is Rs 46.68 lakhs.
2. Tender shall be submitted in tender box kept at corporate office on or before 03-02-2017 up to 10.30 hrs.
3. The period of completion of job will be 90 days( staggered time as per production –shut down schedule) from the date of handover of site. Time is essence of the contract; contractor has to mobilize materials & labour to complete within stipulated time period.
4. The tenderer shall inspect the site of work and understand the scope of work before quoting. No extra amount will be paid on account of misunderstanding either in scope of work, specification, drawings, site conditions etc.
5. All materials required for the work shall be arranged by the contractor unless until specified in Bill of Quantities.
6. The work shall be carried out as per MES-SSR-2009 specifications.
7. This is an item rate contract and the quantities are approximate, but payment will be made only on actual work done based on joint measurement.
8. Four R. A Bills and one Final Bill will be paid. The contractor has to furnish all material bills along with each bill (if any).
9. R.A Bill will be paid within 15 days from the date of certification of Engineer-in-charge. However, Final payment will be made within 30 days after satisfactory completion of work and certification by Engineer-in-charge.
10. a) **Security Deposit (S.D)**: The successful tenderer has to submit 5% of Work order value as a security deposit in the form of D.D/ Bank Guarantee at the time of entering / signing the contract. Further, EMD deposited will be adjusted in 5% Security Deposit & the security deposited will be released after satisfactory completion of work and after certification of Engineer-In- Charge.

EMPLOYER

CONTRACTOR

- b) **Retention Money** : A sum of 5% of gross value of work order will be deducted from each running bill and final bill. The same will be released after the completion of defect liability period of 12 months and after certification of Engineer –In- Charge. Also, contractor can submit Bank Guarantee for equivalent amount in the prescribed format issued by nationalized or scheduled bank and same shall be valid for defect liability period + 3 months claim period.
11. The security and safety rules of MIDHANI to be followed. The contractor shall take care of all labour laws regarding minimum wages, ESI, PF, C.A.R. Policy, Group Insurance etc., Midhani is no way responsible in this respect. Midhani is not liable for any claim in respect of any accidents during the work.
12. (a) MIDHANI reserves the right to operate partial or delete any item specified in BOQ without any compensation to contractor for the items un-operated or deleted.
- (b) If at any time after acceptance of the tender MIDHANI feels that for any reasons whatsoever, if the whole or any part of the contract services is not required to be carried out, notice shall be given in writing of the fact to the contractor and upon receipt of such notice, the contractor shall stop the execution of such services as indicated in the notice forthwith. The contractor shall have no claim to any payment of compensation or otherwise whatsoever on account of any profit or advantage which he might have derived from the execution of the services in full, but which he did not derive in consequence of the foreclosing of the services / contract. Contractor shall be paid at contract rates for the full amount of the work executed including such additional services as may be rendered necessary by said foreclosing.
13. Any new items (viz. supply of material, labour, skilled works etc) will be paid as per (a) or (b) whichever is less:
- a) As per MES-SSR 2010 rates with applicable Percentage Index at that time.  
b) As per market rate analysis.
14. The contractor should not cause any loss or damage to MIDHANI property/or personnel, if any loss or damage is caused the cost of the same will be recovered from the bills by MIDHANI, which will be final.
15. The quantities are subjected to  $\pm 50\%$  variation and the contractor has to carry the work on the same rates, terms and conditions within the variation limits prescribed.
16. If the contractor fails to receive the work order within a week time from the date of intimation to him or if the contractor does not start the work within 3-7 days from the date of handover of site, or if the work is abandoned / stopped without bringing proper notice to Engineer-in-charge, the contract will be terminated and balance work will be carried out at the cost and risk of contractor.
17. Liquidated Damages: - a) If the work is not completed within stipulated time, liquidated damages at 1% per week delay up to maximum of 10% total value of work will be deducted.  
b) If the delays are not attributed to the contractor, the competent authority holds the right to waive off the L.D or reduce the L.D as the case may be.

18. Midhani reserves the right to penalize

- a) If the contractor fails to submit the 5% Security deposit within the stipulated period, then penalty of Rs 1000 per day maximum of 10,000.00 will be collected and further delay will empower MIDHANI to termination of contract and apply risk purchase.
- b) If the contractor fails to receive the work order within 3 days of intimation, then a penalty Rs 500 per day will be levied subjected to maximum of Rs 5000.00. Further delay will empower MIDHANI to termination of contract and apply risk purchase.
- c) Contractor has to maintain "HINDRANCE REGISTER" which is to be certified by both MIDHANI Site engineer and contractor engineer before release of final bill.

19. The offer shall be valid for 3 months from the date of opening of tender.

20. Interested parties may attend tender opening on 03-02-2017 at 11:00 hrs.

21. Incomplete or partially filled tenders will be rejected. Also, conditional offers are liable for rejection. MIDHANI reserves the right to accept or reject any or all tenders without assigning any reasons.

22. Contractor has to maintain site record, hindrance record, record for steel, cement etc.

23. Site has to be cleaned by the contractor before handing over to MIDHANI after completing the work. The final bill will be processed only after obtaining site cleaning certificate from the Engineer-in-charge.

24. The contractor shall bear all levies, taxes including service tax, duties etc., payable or arising from/ out of by virtue of or in connection with and / or incidental to the contract or operation(s) or any other part thereof to be performed by the contractor and the contractor shall indemnify and keep indemnified MIDHANI from and against the same or any default by the contractor in the payment there of.

Yours faithfully,  
For Mishra Dhatu Nigam Limited

**T.RAGHURAM**  
**Addl. General Manager (I/C Purchase)**

DECLARATIONS: - 1) I have seen the site and understood the full scope of work,  
specified in tender, BOQ etc.  
2) I agree to return all the documents along with this offer.

CONTRACTOR  
SIGNATURE AND SEAL

P.S;- 1. All Parties shall attend pre bid meeting on 24-01-2017 at 11.00Hrs in the Purchase Department.

BOQ for Civil works involved in Revamping of 1500T Press, MIDHANI							
SI.No	Description of work	unit	Quantity	Rate		Amount	
				Rs	Ps	Rs	Ps
1	Dismantling RCC including taking out reinforcement in ground floors, and stacking at 50m lead. Rate also including disposal upto lead of 500m complete.	Cu.m	375.00				
2	Labour charges for removal of old inserts like MS plates, angles, channels etc (at all heights & levels as per site condition) including the cost of gas cutting tools set, cylinders etc as per instructions of Engineer-in-charge. The cost includes removal, loading, unloading stacking of materials wherever directed upto a distance of 500m.	M.T.	10.00				
3	Providing & laying RCC M35 Design Mix of specified grade excluding the cost of centering & shuttering all work at all levels as indicated in drawing including cost of mixing, placing, compaction, vibration, pumping, consolidation, curing complete, walls, staircase etc with 20mm & down size metal at all levels .	Cu.m	375.00				
4	Labour charges for cutting, bending, tying TMT reinforcement bars with binding wire, placing in position and maintaining openings for pockets, inserts etc are in the scope of contractor. The TMT bars is free of supply from MIDHANI. However, the cost of binding wire is in the scope of contractor. The reinforcement work is to be carried as per the schedule given by the Engineer-in-charge. ( 8,10,12,16,20,25mm dia).	kg	26250.00				

EMPLOYER

CONTRACTOR

5	Providing & fixing Centring & Shuttering including strutting, propping etc., & removal of form for : sides of concrete foundation, footings, bases of columns, raft and raft beams, sides and soffits (if any) of foundation and plinth beams; and similar work; vertical or to batter.	Sqm	1875.00		
6	Providing and grouting with Non-shrink Cementious previous grout material in required size of packing's (Fosroc Chemical : Conbextra GP2) as per the manufacture specifications (50% chips allowance)	Cu.m	12.00		
7	Providing, fixing, removal of pockets of size 100x150x300mm to 500x600x1000mm for foundation. The shuttering material used for making & fixing of pockets shall be removed by the contractor without damage to pockets. If any damage occurred, the same shall be rectified by the contractor at free of cost. Responsibility of Contractor is to handover the pockets to Forge shop engineer with proper marking of centre lines, levels etc.	No.s	40.00		
8	Providing & Water proofing plaster in 20mm thick rich mortar C.M(1:4) in Main foundation including void sealing with pressure grouting at every 0.6m centre to centre both ways including mixing of water proofing compound( at all heights & levels and as per instruction of Engineer-in-Charge)	Sqm	500.00		
9	Providing & fixing of insert plates - M.S Steel Insert plates, Angles, including caps, bases, splices etc. built-up from two or more beam or channel sections or angles with plates, including all lattice bars, stiffeners, gusset plates, kerb angles, channels and beams etc ( at all heights & levels and as per instruction of Engineer-in-Charge)	Kg	1350.00		
10	Supply of				
	a) Unskilled labour	No.s	25.00		
	b) Skilled labour	No.s	30.00		
<b>Total Amount</b>					

EMPLOYER

CONTRACTOR